

City of Globe
150 N. Pine Street
Globe, AZ 85501

ADDENDUM #2
TO THE JUNE 25, 2025
INVITATION TO BID
FOR THE
GLOBE SKATE PARK IMPROVEMENTS PROJECT

Addendum #1 Date: 07/23/2025

This addendum, and all the information contained herein and attached hereto, shall become as fully a part of the INVITATION TO SUBMIT BIDS and other BID/CONTRACT DOCUMENTS for the **CITY OF GLOBE SKATE PARK IMPROVEMENTS PROJECT**, as if therein included, and shall take full and complete preference over anything therein contained to the contrary.

Acknowledgement: Each Bidder shall acknowledge receipt of this Addendum in their bid package on the Bid Form.

Each bidder, firm, contractor, subcontractor, or supplier shall be responsible for reading each and every item in this addendum to ascertain to what extent and in what manner it affects the work that they are interested in.

RESPONSES RECEIVED TO QUESTIONS FROM PROSPECTIVE BIDDERS

1. Question: Bid schedule items 4 through 17 are skate park equipment with quantities. Does this list cover the verbiage on drawings 3 of 5 "bid to include the purchase and installation of skate ramp equipment to best utilize the 729SY space"? Is there specific skate park equipment that Globe prefers?

Answer: Please refer to the attachment included with addendum no. 1 – diagram of the skate park layout and the list of equipment. The skate park layout included in Addendum No. 1 is only one idea. Other designs of the skate equipment layouts are up for consideration.

2. Question: Drawing 1 of 5 has quantities with construction notes crossed out in red and other construction notes boxed in green, the same construction notes are shown on drawing 3 of 5 with no markups. Please advise on what construction notes are to be used for bidding. Drawing 3 of 5 has red X's over the new masonry retaining wall and two pads for picnic tables. Please confirm the retaining wall is not included in the project and that 3 slabs for picnic tables are to be factored per the bid schedule.

Answer: Drawing 1 of 5 has the correct construction notes. The retaining wall is not part of this project. As noted in Addendum No. 1, the picnic table pads and sidewalks are the priority items. The city is willing to lose

pieces of skate equipment if necessary, hence why other design of the park equipment layout are up for consideration.

3. Question: Bid is for picnic table pads only, picnic tables are not part of the scope, correct?

Answer: Correct. Bid is for picnic table pads only.

4. Question: Is there a detail on how to finish the concrete slab at the chain-link fencing?

Answer: The city is looking for a “brushed” finish.

5. Question: Is permitting required?

Answer: No permits are required.

6. Question: Page 70 of 80, Item No. 01 Concrete sidewalk states PCC sidewalk shall be constructed to a minimum of 4” thick; further down it states “Construct new 5” depth of PCC sidewalk on the compacted subgrade.” Details on drawing 4 of 5 show the depth of the concrete slab at 4”. Please confirm the depth of the sidewalk is 4” or 5”.

Answer: All sidewalks are to be done to MAG Standard Detail 230 which calls out a 4-inch depth.

Attachments:

- 07-23-2025 Bid Schedule

*** End of Addendum #2 ***

BID SCHEDULE – 7/23/2025

Name of Contractor/Bidder: _____

Email Address: _____

NO.	ITEM DESCRIPTION	HEIGHT	WIDTH	LENGTH	ITEM BID TOTAL
1	RAIL	1.5	0.2'	12.0'	\$
2	BANK RAMP	3	4.0'	7.0'	\$
3	PYRAMID CORNER (BANK RAMP) 90 DEGREE	3	7.3'	7.3'	\$
4	BANK RAMP	3.0'	4.0'	11.0'	\$
5	BANK RAMP	3.0'	4.0'	11.0'	\$
6	QUARTER PIPE	3.0'	4.0'	10.0'	\$
7	QUARTER PIPE	3.0'	4.0'	10.0'	\$
8	PYRAMID SECTION (WEDGE)	2.0'	6.0'	20.0'	\$
9	BANK RAMP (WEDGE)	1	4.0'	4.0'	\$
10	BANK RAMP (WEDGE)	1	4.0'	4.0'	\$
11	GRINDBOX (2' WIDE)	2	2.0'	20.0'	\$
12	STAIRS	1	4.0'	4.0'	\$
13	GRINDBOX	1	4.0'	12.0'	\$
14	STAIRS	1	4.0'	1.0'	\$
15	QUARTER PIPE	2	4.0'	5.0'	\$

NO.	ITEM DESCRIPTION	HEIGHT	WIDTH	LENGTH	ITEM BID TOTAL
16	QUARTER PIPE	2	4.0'	5.0'	\$
17	QUARTER PIPE	2	4.0'	5.0'	\$
18	QUARTER PIPE	2	4.0'	5.0'	\$
19	GRIND RAIL (ROUND)	2.0'	2"	18.0'	\$
20	WEDGE, FLAT, STAIR	2.0'	10.0'	30.0'	\$
21	PLANTER (2' WIDE)	3.5	2.0'	24.5'	\$
22	BANK RAMP (WEDGE 2' WIDE)	2	2.0'	8.0'	\$
23	BANK RAMP (WEDGE)	2.0'	8.0'	8.0'	\$
24	BANK RAMP (WEDGE)	2.0'	8.0'	8.0'	\$
25	GRIND RAIL, KINKED (ROUND)	1.5'	2"	18.0	\$
26	QUARTER PIPE	4	4.0'	11.0'	\$
27	QUARTER PIPE	4	4.0'	11.0'	\$
28	QUARTER PIPE	4	4.0'	11.0'	\$
29	BANK RAMP	4	4.0'	13.0'	\$
30	BANK RAMP	4	4.0'	13.0'	\$
31	QUARTER PIPE	4	4.0'	11.0'	\$
32	QUARTER PIPE	4	4.0'	11.0'	\$
33	QUARTER PIPE	4	4.0'	11.0'	\$

NO.	ITEM DESCRIPTION	HEIGHT	WIDTH	LENGTH	ITEM BID TOTAL
34	SAFETY HANDRAIL			42 LF	\$
35	4" MINIMUM THICKNESS SIDEWALK EXTENSION (120'X5'; 600 SQFT)			600 SQFT	
36	ADA COMPLIANT PICNIC TABLE PADS (3 PADS TOTAL)				\$
37	MOBILIZATION				\$
TOTAL BID AMOUNT					\$